



6106 Corporate Park Drive
Browns Summit, NC 27214
Phone: (336) 375-1989
Fax: (336) 375-1801

March 23, 2011

Mr. Michael W. Johnson
Southampton County Administrator
26022 Administration Center Drive
Courtland, VA 23837

Project: Turner Tract - Phase 1 Grading

Subject: Request for Change Order

Dear Mr. Johnson,

I am writing to request a Contract Change Order for \$73,727 Lump Sum for temporary slope drains on Basins 1 and 2 on the subject project. A cost breakdown is detailed below for your convenience.

Subcontractor Slope Drain Cost - \$66,590

Seed Credit - \$1,200

Subtotal - \$65,390

Administrative Mark Up (10%) - \$6,539

Subtotal - \$71,929

Bond Fee (2.5%) - \$1,798

Total - \$73,727

If you have any questions or concerns regarding the provided request please feel free to give me a call at (336) 430 - 1719.

Sincerely,
Shamrock Environmental Corporation

David J. Schuster, P.E.
Project Manager

Attachment

Copy : Stephen Quina, Timmons Group

CROWDER & WHITE CONTRACTING, LLC.

Excavating and Grading Contractor

30065 General Thomas Hwy

Franklin, Virginia 23851

757-569-0898

PROPOSAL

March 21, 2011

Shamrock Environmental Corporation

6101 Corporate Place Drive

Browns Summit, NC 27214

Attn: David Schuster, P.E.

Re: Diversion/Slope Drains

We propose to furnish all supervision, labor, materials and equipment to furnish the following:

Mobilize construction equipment and materials	\$ 500.00
Layout diversion channel and slope drain locations	\$ 750.00
Construct approximately 2,250 lf of diversion channel and ridge as shown on Timmons Group, Turner Tract Phase 1 Grading Plan, Slope Drain Plan dated 1/6/11.	\$ 4,500.00
Install 16 ea. – single wall 24” slope drain piping as per same drawings	\$ 44,500.00
Seed all areas disturbed by our construction activities with a switch grass/rye/foxtail millet grass mixture.(see notes)	\$ 4,400.00
Furnish and install EC-2 matting over compacted diversion ridge (approximately 16’ wide)	\$ 5,000.00
Install 16 ea. straw bale inlet protection as shown on Dwg provide by Shamrock	\$ 1,940.00
Provide 1 yr maintenance for our scope of work	\$ 5,000.00
Total Lump Sum Cost:	\$ 66,590.00

Exclusions and Notes:

CWC has included a 22.5 degree bend in the slope drain piping at the top of the pond slope as well as an additional bend at the top and bottom (total of 3) of the aquatic bench to better align the proposed pipe with the existing pond slope. Tie downs will be used on each drain to secure pipes in place.

Provide 1 year of maintenance for our scope of work as well as slope repair on the basins should the drains fail. Repairs shall consist of regrading, reseeding and rematting the repaired areas.

Grass seed will be applied as; 50% switch grass @ 50lb/ac. and 25% winter rye @ 25 lbs/ac., and 25% foxtail millet @ 25 lbs/ac.

We will be using an Excel Regular Excelsior EC-2 matting 16'width in lieu of the Coconut matting requested earlier.

Thank you for the opportunity to quote this work. If we can be of further service please let us know.

Sincerely,

Matthew W. Crowder,
President



6106 Corporate Park Drive
Browns Summit, NC 27214
Phone: (336) 375-1989
Fax: (336) 375-1801

March 23, 2011

Mr. Michael W. Johnson
Southampton County Administrator
26022 Administration Center Drive
Courtland, VA 23837

Project: Turner Tract - Phase 1 Grading

Subject: Request for Change Order

Dear Mr. Johnson,

I am writing to request a Contract Change Order for \$5,738 for slope stabilization on the CMS on the subject project. This price is based on a unit rate of \$3,800 per acre for 1.51 acres for the areas depicted in the attached Exhibit 1.

If you have any questions or concerns regarding the provided request please feel free to give me a call at (336) 430 - 1719.

Sincerely,
Shamrock Environmental Corporation

A handwritten signature in cursive script that reads "David J. Schuster".

David J. Schuster, P.E.
Project Manager

Attachment

Copy: Stephen Quina, Timmons Group